



LOCATION MAP  
NOT TO SCALE



**SITE DATA:**

OWNER / DEVELOPER: CONTE HOMES, INC.  
1420 JOURNEY'S END ROAD  
TOWN OF YORKYOWN  
CROTON-ON-HUDSON, NY, 10520

PROJECT LOCATION: 1550 JOURNEYS END ROAD  
R1-200, ONE-FAMILY RESIDENTIAL  
SECTION 69.06, BLOCK 1, LOT 10

EXISTING TOWN ZONING: R1-200, ONE-FAMILY RESIDENTIAL  
PROPOSED USE: R1-200, ONE-FAMILY RESIDENTIAL



TOWN TAX MAP DATA: 9.09 ACRES (396,091 SF)  
SITE AREA: PUBLIC SEWERS  
SEWAGE FACILITIES: PUBLIC WATER FACILITIES  
WATER FACILITIES: PUBLIC WATER FACILITIES

**ZONING SCHEDULE:**

ZONING DISTRICT: R1-200, ONE-FAMILY RESIDENTIAL			
DIMENSIONAL REGULATIONS:	REQUIRED	PROVIDED	VARIANCE REQUIRED
<b>MINIMUM SIZE OF LOT:</b>			
MINIMUM LOT AREA:	200,000 SF.	396,091 SF.	NONE
MINIMUM LOT WIDTH:	200 FT.	350 FT.	NONE
MINIMUM LOT DEPTH:	200 FT.	1123 FT.	NONE
MINIMUM ROAD FRONTAGE:	200 FT.	357 FT.	NONE
<b>MINIMUM YARD DIMENSIONS:</b>			
PRINCIPAL BUILDING:	75' / 100 FT. (1)	75' FT.	25' VARIANCE
FRONT YARD SETBACK:	75 FT.	1029 FT.	NONE
REAR YARD SETBACK:	30 FT.	140 FT.	NONE
ONE SIDE YARD SETBACK:	80 FT.	293 FT.	NONE
COMBINED SIDE YARD SETBACK:			
<b>MAXIMUM % OF LOT TO BE OCCUPIED:</b>			
TOTAL BUILDING COVERAGE:	10% OF LOT AREA	0.5 % OF LOT AREA	NONE
MINIMUM USABLE FLOOR AREA OF D.U.	1,200 SF	2,010 FT.	NONE
<b>MAXIMUM HEIGHT:</b>			
PRINCIPAL BUILDING - FEET:	35 FT.	35 FT.	NONE

**ZONING REGULATION NOTES:**


- ON STREETS WITH LESS THAN A 50-FOOT RIGHT-OF-WAY, THE FRONT YARD SETBACK SHALL BE MEASURED FROM THE CENTER LINE OF THE EXISTING ROADWAY AND 25 FEET SHALL BE ADDED TO THE REQUIRED FRONT YARD SETBACK.
- WHERE PUBLIC SEWERS ARE NOT AVAILABLE, THE MAXIMUM FLOOR AREA RATIO SHALL NOT EXCEED 1/2 THE FIGURES SHOWN.



LOCATION PLAN  
SCALE: 1" = 200'


**LEGEND**

- EXISTING GRADING
- EXISTING SPOT GRADE
- PROPOSED GRADING
- PROPERTY LINE / RIGHT OF WAY
- PROPOSED ROAD CENTERLINE
- PROPOSED CURB
- EDGE OF WETLAND
- 100' WETLAND BUFFER
- EXISTING STONE WALL
- PROPOSED DRAINAGE LINE
- PROPOSED CATCH BASIN
- PROPOSED DRAINAGE MANHOLE
- PROPOSED FOOTING DRAIN
- PROPOSED SEWER FORCE MAIN
- PROPOSED HOUSE AND DRIVE
- PROPOSED RETAINING WALLS



**NOTE:**  
1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY WARD CARPENTER ENGINEERS INC., DATED 10/9/17. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



**Site Design Consultants**  
Civil Engineers • Land Planners  
251-F Underhill Avenue, Yorktown Heights, NY 10598  
(914) 962-4488 - Fax: (914) 962-7386  
www.sitedesignconsultants.com



Revisions:	No.	Date	Comments
	1.	12-2-18	Driveway relocation
	2.	2-01-19	House relocation


SCALE:	1" = 20'
DRAWN BY:	MD
DATE:	9-18-18

**SITE PLAN**

SITE PLAN PREPARED FOR  
**CONTE HOMES, INC.**  
1550 JOURNEY'S END ROAD  
Westchester County, NY  
Town of Yorktown


COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS. ALL RIGHTS RESERVED

E:\2012\15-60 VICTOR CONTE - JOURNEY'S END ROAD ENGINEERING\CD\CD17-60 VICTOR CONTE\15-60 VICTOR CONTE SITE SEPT 11 2012 3:18:52 PM



**LEGEND**


	EXISTING GRADING
	EXISTING SPOT GRADE
	PROPERTY LINE / RIGHT OF WAY
	EDGE OF WETLAND
	100' WETLAND BUFFER
	EXISTING STONE WALL
	SOIL TYPE



**SAFE DIG**  
 Before You Dig, Drill or Blast!  
 Call 811  
 811 is a free service that helps you find underground utilities before you dig. It's the first step to a safe dig. Call 811 at least 48 hours before you dig. For more information, visit www.call811.com

**NOTE:**  
 1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY WARD CARPENTER ENGINEERS INC., DATED 10/9/17. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



**Site Design Consultants**  
 Civil Engineers • Land Planners  
 251-F Underhill Avenue, Yorktown Heights, NY 10598  
 (914) 962-4488 - Fax: (914) 962-7386  
 www.sitedesignconsultants.com



Revisions:

No.	Date	Comments
1	12-2-18	Driveway relocation

SCALE: 1" = 20'

DRAWN BY: MD

DATE: 9-18-18

**EXISTING CONDITIONS PLAN**

SITE PLAN PREPARED FOR  
**CONTE HOMES, INC.**  
 1550 JOURNEY'S END ROAD  
 Town of Yorktown  
 Westchester County, NY

PROJECT # 17-50  
 COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS. ALL RIGHTS RESERVED



**LEGEND**


	222	EXISTING GRADING
	222.8	EXISTING SPOT GRADE
	200	PROPOSED GRADING
		PROPERTY LINE / RIGHT OF WAY
		EDGE OF WETLAND
		100' WETLAND BUFFER
		EXISTING STONE WALL
		PROPOSED CATCH BASIN
		PROPOSED DRAINAGE MANHOLE
		PROPOSED FOOTING DRAIN
		PROPOSED ROOF DRAIN
		PROPOSED HOUSE AND DRIVE
		PROPOSED RETAINING WALLS
		PROPOSED SOIL STOCKPILES
		PROPOSED SILT FENCE
		PROPOSED STABILIZED CONSTRUCTION ENTRANCE
		PROPOSED LIMIT OF DISTURBANCE



**NOTE:**  
 1. THIS IS NOT A SURVEY. ALL SURVEY INFORMATION SHOWN ON THIS PLAN HAS BEEN TAKEN FROM SURVEY MAP PREPARED BY WARD CARPENTER ENGINEERS INC., DATED 10/9/17. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.

E:\PROJECTS\2018\CONTE-HOMES-INC\CONTE-SITE-SEPT18-2018.DWG (11/20/18) 2:18:52 PM

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



**Site Design Consultants**  
 Civil Engineers • Land Planners  
 251-F Underhill Avenue, Yorktown Heights, NY 10598  
 (914) 962-4488 - Fax: (914) 962-7386  
 www.sitedesignconsultants.com



Revisions:

No.	Date	Comments
1	12-2-18	Driveway relocation
2	2-01-19	House relocation

SCALE: 1" = 20'	DRAWN BY: MD	DATE: 9-18-18
-----------------	--------------	---------------

**EROSION & SEDIMENT CONTROL PLAN**

SITE PLAN PREPARED FOR  
**CONTE HOMES, INC.**  
 1550 JOURNEY'S END ROAD  
 Town of Yorktown  
 Westchester County, NY

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS. ALL RIGHTS RESERVED

**GENERAL EROSION CONTROL NOTES:**

- Contractor shall be responsible for compliance with all sediment and erosion control practices. The sediment and erosion control practices are to be installed prior to any major soil disturbances, and maintained until permanent protection is established. Road surface flows from the site should be dissipated with tracking pad or appropriate measures during adjacent road shoulder grading. Contractor is responsible for the installation and maintenance of all soil erosion and sedimentation control devices throughout the course of construction.
- Catch basin inlet protection must be installed and operating at all times until tributary areas have been stabilized. When possible flows should be stabilized before reaching inlet protection structure. Timely maintenance of sediment control structures is the responsibility of the Contractor.
- All structures shall be maintained in good working order at all times. The sediment level in all sediment traps shall be closely monitored and sediment removed promptly when maximum levels are reached or as ordered by the engineer. All sediment control structures shall be inspected on a regular basis, and after each heavy rain to insure proper operation as designed. An inspection schedule shall be set forth prior to the start of construction.
- The locations and the installation times of the sediment capturing standards shall be as specified in these plans, as ordered by the Engineer, and in accordance with the latest edition of the "New York Standards and Specifications for Erosion and Sediment Control" (NYSSESC).
- All topsoil shall be placed in a stabilized stockpile for reuse on the site. All stockpile material required for final grading and stored on site shall be temporarily seeded and mulched within 7 days. Refer to soil stockpile details.
- Any disturbed areas that will be left exposed more than 7 days and not subject to construction traffic, shall immediately receive temporary seeding. Mulch shall be used if the season prevents the establishment of a temporary cover. Disturbed areas shall not be limed and fertilized prior to temporary seeding.
- All disturbed areas within 500 feet of an inhabited dwelling shall be wetted as necessary to provide dust control.
- The contractor shall keep the roadways within the project clear of soil and debris and is responsible for any street cleaning necessary during the course of the project.
- Sediment and erosion control structures shall be removed and the area stabilized when the drainage area has been properly stabilized by permanent measures.
- All sediment and erosion control measures shall be installed in accordance with current edition of NYSSESC.
- All regraded areas must be stabilized appropriately prior to any rock blasting, cutting, and/or filling of soils. Special care should be taken during construction to insure stability during maintenance and integrity of control structures.
- Any slopes graded at 3:1 or greater shall be stabilized with erosion blankets to be stacked into place in accordance with the manufacturers requirements. Erosion blankets may also be required at the discretion of Town officials or Project Engineer. When stabilized blanket is utilized for channel stabilization, place all of the volume of seed mix prior to laying net, or as recommended by the manufacturer.
- To prevent heavy construction equipment and trucks from tracking soil off-site, construct a pervious crushed stone pad. Locate and construct pads as detailed in these plans.
- Contractor is responsible for controlling dust by sprinkling exposed soil areas periodically with water as required. Contractor to supply all equipment and water.
- Contractor shall be responsible for construction inspections as per NYSDEC GP-0-15-002 and Town of Yorktown Code.

**MAINTENANCE OF TEMPORARY EROSION AND SEDIMENT CONTROL STRUCTURES:**

N.Y.S.D.E.C. GP-0-15-002 EXPOSURE RESTRICTIONS - States that any exposed earthwork shall be stabilized in accordance with the guidelines of this plan.

- Trees and vegetation shall be protected at all times as shown on the detail drawing and as directed by the Engineer.
- Care should be taken so as not to channel concentrated runoff through the areas of construction activity on the site.
- Fill and site disturbances should not be created which causes water to pond off site or on adjacent properties.
- Runoff from land disturbances shall not be discharged or have the potential to discharge off site without first being intercepted by a control structure, such as a sediment trap or silt fence. Sediment shall be removed before exceeding 50% of the retention structure's capacity.
- For finished grading, adequate grade shall be provided so that water will not pond on lawns for more than 24 hours after rainfall, except in swale flow areas which may drain for as long as 48 hours after rainfall.
- All swales and other areas of concentrated flow shall be properly stabilized with temporary control measures to prevent erosion and sediment travel. Surface flows over cut and fill areas shall be stabilized at all times.
- All sites shall be stabilized with erosion control materials within 7 days of final grading.
- Temporary sediment trapping devices shall be removed from the site within 30 days of final stabilization.

**MAINTENANCE OF PERMANENT CONTROL STRUCTURES DURING CONSTRUCTION:**

The stormwater management system and outlet structure shall be inspected on a regular basis and after every rainfall event. Sediment build up shall be removed from the inlet protection regularly to insure detention capacity and proper drainage. Outlet structure shall be free of obstructions. All piping and drain inlets shall be free of obstruction. Any sediment build up shall be removed.

**MAINTENANCE OF CONTROLS AFTER CONSTRUCTION:**

Controls (including respective outlet structures) should be inspected periodically for the first few months after construction and on an annual basis thereafter. They should also be inspected after major storm events.

**DEBRIS AND LITTER REMOVAL:**

Twice a year, inspect outlet structure and drain inlets for accumulated debris. Also, remove any accumulations during each mowing operation.

**STRUCTURAL REPAIR/REPLACEMENT:**

Outlet structure must be inspected twice a year for evidence of structural damage and repaired immediately.

**EROSION CONTROL:**

Unstable areas tributary to the basin shall immediately be stabilized with vegetation or other appropriate erosion control measures.

**SEDIMENT REMOVAL:**

Sediment should be removed after it has reached a maximum depth of five inches above the stormwater management system floor.

**TOPSOIL:**

Existing topsoil will be removed and stored in piles sufficiently as to avoid mixing with other excavation. Stockpiles shall be surrounded by erosion control as outlined on these plans. The furnishing of new topsoil shall be of a better or equal to the following criteria (SS713.01 NYSDOT):

- The pH of the material shall be 5.5 to 7.6.
- The organic content shall not be less than 2% or more than 70%.
- Gradation:

SIEVE SIZE	% PASSING BY WGT.
2 INCH	100
1 INCH	85 TO 100
1/4 INCH	65 TO 100
NO. 200 MESH	20 TO 80

**PERMANENT VEGETATIVE COVER:**

- Site preparation:
  - Install erosion control measures.
  - Scarify compacted soil areas.
  - Lime as required to pH 6.5.
  - Fertilize with 10-6-4 4 lbs/1,000 S.F.
  - Incorporate amendments into soil with disc harrow.
- Seed mixtures for use on swales and cut and fill areas.

MIXTURE	LBS/ACRE
ALT. A	
KENTUCKY BLUE GRASS	20
CREEPING RED FESCUE	28
RYE GRASS OR REDTOP	5
ALT. B	
CREEPING RED FESCUE	20
REDDOP	2
TALL FESCUE/SMOOTH BLOOMGRASS	20
- SEEDING
  - Prepare seed bed by raking to remove stones, twigs, roots and other foreign material.
  - Apply soil amendments and integrate into soil.
  - Apply seed uniformly by cyclone seeder culti-packer or hydro-seeder at rate indicated.
  - Stabilize seeded areas in drainage swales.
  - Irrigate to fully saturate soil layer, but not to dislodge planting soil.
  - Seed between April 1st and May 15th or August 15th and October 15th.
  - Seeding may occur May 15th and August 15th if adequate irrigation is provided.

**TEMPORARY VEGETATIVE COVER:**

- SITE PREPARATION:**
- Install erosion control measures.
  - Scarify areas of compacted soil.
  - Fertilize with 10-10-10 at 400/acre.
  - Lime as required to pH 6.5.

SEED SPECIES:	LBS/ACRE
Rapidly germinating annual ryegrass (or approved equal)	20
Perennial ryegrass	20
Cereal oats	36

SEEDING:  
Same as permanent vegetative cover

**OWNER / OPERATOR CERTIFICATION**

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a Class A misdemeanor pursuant to Section 210.45 of the Penal Law."

Name (please print): \_\_\_\_\_  
 Title: \_\_\_\_\_  
 Date: \_\_\_\_\_  
 Address: \_\_\_\_\_  
 Phone: \_\_\_\_\_  
 E-mail: \_\_\_\_\_  
 Signature: \_\_\_\_\_

**MAINTENANCE SCHEDULE:**

	DAILY	WEEKLY	MONTHLY	AFTER RAINFALL	NECESSARY TO MAINTAIN FUNCTION	AFTER APPROVAL OF INSPECTOR
SILT FENCE	___	___	INSP.	INSP.	CLEAN/ REPLACE	REMOVE
WHEEL CLEANER	CLEAN	___	___	___	REPLACE	REMOVE
INLET PROTECTION	___	INSP.	INSP.	CLEAN	REPLACE	REMOVE

**CONTRACTOR CERTIFICATION STATEMENT**

Certification Statement - All contractors and subcontractors as identified in a SWPPP, by the Owner or Operator, in accordance with Part III.A.5 of the SPDES General Permit for Stormwater Runoff from Construction Activity, GP-0-15-002, dated January 29, 2015, Page 10 of 40, shall sign a copy of the following Certification Statement before undertaking any construction activity at the Site identified in the SWPPP:

"I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the Qualified Inspector during a site inspection. I also understand that the Owner or Operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System ("SPDES") General Permit for Stormwater Discharge from Construction Activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings."

Individual Contractor: \_\_\_\_\_  
 Name and Title (please print): \_\_\_\_\_  
 Signature of Contractor: \_\_\_\_\_  
 Company / Contracting Firm: \_\_\_\_\_  
 Name of Company: \_\_\_\_\_  
 Address of Company: \_\_\_\_\_  
 Telephone Number / Cell Number: \_\_\_\_\_  
 Site Information: \_\_\_\_\_  
 Address of Site: \_\_\_\_\_  
 Today's Date: \_\_\_\_\_


**Construction Sequence**

Refer to the Plan Set for all plans and details which relate to Construction Sequence.


- A licensed surveyor must define infrastructure locations, limits of disturbance, stormwater basin limits, and grades in the field prior to start of any construction. Limits of disturbance shall be marked with the installation of construction fence or approved equal.
- Install all perimeter erosion control measures, construction entrance as shown on the Erosion and Sediment Control Plan and the associated Details.
- Cut and clear trees within work area. Timbered trees, wood chips, and stumps shall be removed off-site. Strip site and place topsoil in stockpile locations shown on the plan. Demolish existing building and other existing improvements including Driveway, walkways, walls, and pavings.
- Start construction of project access points, set-up staging areas and install anti-tracking pads as shown on Erosion and Sediment Control Plan.
- Begin rough grading the site. Contractor to limit exposure of denuded soils by providing temporary stabilization for work areas that will remain undisturbed for over seven (7) days.
- Rough grade driveway and building.
- Begin excavation of building foundations, wall, and utilities. Protect open excavations. Where applicable, place fill on the up-slopes and side edges of fill area. Fill should be pushed in place and stabilized with tracking perpendicular to the slope. Place soil stockpiles in locations shown on the Erosion and Sediment Control Plans and associated Details.
- Begin construction of Building.
- Upon completion of foundation, backfill to grade and immediately stabilize areas that will not receive traffic or disturbance within seven (7) days.
- Begin the excavation and installation of utilities and drainage system. Protect trenches and open excavations from erosion. All drainage inlets shall be protected from sediment entering. There shall be no direct unfiltered discharge into the stormwater systems. The stormwater outlet shall be blocked until all upstream areas have been permanently stabilized.
- During building and site construction maintain and re-establish as required erosion control and stabilization measures as required by the site plan and details.
- Install base course of Item 4 for driveway. Stabilize all open areas with seed and mulch.
- Construct remainder of driveway. Install asphalt pavement, and Flagstone walkway. Once asphalt is installed, drainage outlet may be unblocked.
- Backfill, grade, place final soil topping and put in place permanent vegetative cover over all disturbed areas, landscape beds, slopes, etc.
- Once site stabilization has taken place (An area shall be considered to have achieved final stabilization when it has a minimum uniform 70% perennial vegetative cover or other permanent non-vegetative cover with a density sufficient to resist accelerated surface erosion and subsurface characteristics sufficient to resist sliding and other movements), remove all temporary erosion and sediment controls.

**Winter Stabilization Notes:**




- If construction activities are expected to extend into or occur during the winter season the contractor shall anticipate proper stabilization and sequencing. Construction shall be sequenced such that wherever possible areas of disturbance that can be completed and permanently stabilized shall be done by applying and establishing permanent vegetative cover before the first frost. Areas subject to temporary disturbance that will not be worked for an extended period of time shall be treated with temporary seed, mulch.




**E-1 INLET PROTECTION DETAIL**  
NOT TO SCALE




**E-2 SOIL STOCKPILE DETAIL**  
NOT TO SCALE




**E-5 STABILIZED CONSTRUCTION ENTRANCE DETAIL**  
NOT TO SCALE




**E-3 EROSION BLANKET AND ANCHOR DETAIL**  
NOT TO SCALE



**E-4 TREE TRUNK ARMOR / TREE PROTECTION DETAIL**  
NOT TO SCALE



**E-6 SILT FENCE DETAIL**  
NOT TO SCALE



**Site Design Consultants**  
 Civil Engineers • Land Planners  
 251-F Underhill Avenue, Yorktown Heights, NY 10598  
 (914) 962-4488 - Fax: (914) 962-7386  
 www.sitedesignconsultants.com




Revisions:	No.	Date	Comments
	1	12-2-18	Driveway relocation
	2	2-01-19	House relocation

SCALE: N/A  
 DRAWN BY: MD  
 DATE: 9-18-18


**EROSION & SEDIMENT CONTROL DETAILS**

SITE PLAN PREPARED FOR  
**CONTE HOMES, INC.**  
 1550 JOURNEY'S END ROAD  
 Westchester County, NY  
 Town of Yorktown


NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.



**D-1** ROOF & FOOTING DRAIN CONNECTION DETAIL  
NOT TO SCALE




**R-1** TYPICAL DRIVEWAY SECTION  
NOT TO SCALE




**NOTES:**  
1. All pipes must be cut flush with inside walls.  
2. Drain manhole shall be precast as manufactured by Fort Miller, or approved equal.  
3. Where depth of manhole exceeds 10 ft, inside dimension shall be 60".  
4. Pre-cast sections shall be in accordance with "Pre-cast Reinforced Manhole Sections", A.S.T.M. designation C-478, latest revision. Minimum compressive strength shall be 4000 psi. Structures shall be rated for h-20 vehicle loading.

**D-2** PRECAST DRAIN INLET DETAIL  
NOT TO SCALE




**NOTES:**  
1. Pipe shall be laid and connected in the bedding which shall consist of:  
A. Compacted existing subsoil when laid above ground water or;  
B. 3/4" crushed stone when laid below ground water.  
2. If subsoil is determined to be unsuitable by the Engineer, all unsuitable material shall be removed for at least 2'-6" below the pipe invert or twice the pipe diameter, whichever is greater, and replaced with compacted bedding material.

**D-3** STORM PIPE BEDDING DETAIL  
NOT TO SCALE




**NOTES:**  
1. The foundation area shall be cleared of trees, stumps, sod, loose rock, or other objectionable materials.  
2. The cross section shall be excavated to the neat lines and grades shown on the plans. Over excavated areas shall be backfilled with moist soil compacted to the density of the surrounding material.  
3. Filter, bedding, and rock riprap shall be placed to line and grade in the manner specified.  
4. No abrupt deviations from design grade or horizontal alignment shall be permitted.  
5. Construction operations shall be done in such a manner that erosion, air and water pollution will be minimized and held within legal limits. All disturbed areas shall be vegetated or otherwise protected against soil erosion.

**SW-1** STONE RIP-RAP LEVEL-LIP SPREADER DETAIL  
NOT TO SCALE



**NOTES:**  
1. The top of the well casing shall be set a minimum of 2 ft above the 100 yr high-water level or 18" above finished ground surface, whichever is greater.  
2. A minimum of 4 feet of cover shall be provided over the water service line.

**S-1** DRILLED WELL DETAIL  
NOT TO SCALE



PROPOSED DRIVEWAY  
VERT. SCALE: 1" = 2'  
HORIZ. SCALE: 1" = 20'



**Site Design Consultants**  
Civil Engineers • Land Planners  
251-F Underhill Avenue, Yorktown Heights, NY 10598  
(914) 962-4488 - Fax: (914) 962-7386  
www.sitedesignconsultants.com



Revisions:	No.	Date	Comments
	1	12-2-18	Driveway relocation
	2	2-01-19	House relocation

SCALE: N/A  
DRAWN BY: MD  
DATE: 9-18-18

**DETAILS**


SITE PLAN PREPARED FOR  
**CONTE HOMES, INC.**  
1550 JOURNEY'S END ROAD  
Westchester County, NY  
Town of Yorktown

E:\2018\1550 JOURNEY'S END ROAD\ENGINEERING\CAD\CAD\1550 JOURNEY'S END ROAD\CONTE SITE\SETUP\2-18-19\DWG\11062012.3-18-19.dwg

NOTE: UNAUTHORIZED ALTERATIONS OR ADDITIONS TO THIS DRAWING IS A VIOLATION OF SECTION 7209 (2) OF THE NEW YORK STATE EDUCATION LAW.

COPYRIGHT © 2012 BY SITE DESIGN CONSULTANTS. ALL RIGHTS RESERVED






**PLAN VIEW**


**NOTES:**

- Bottom of distribution box must be level and firmly supported below frost line.
- Distribution box footing to extend to 36" below ground level.
- Distribution box shall be constructed of waterproofed masonry construction.
- Tight joint pipe shall be used from septic tank to box and between all boxes.
- Maximum cover above distribution boxes shall be 12 inches.
- Distribution box shall have not less than two outlets with one outlet for each lateral.
- All outlets shall be set at the same elevation.
- Baffles to ensure equal distribution will be required.
- All outlet pipes shall be cut flush with inside of distribution box.




**NOTES:**

- Forceman to be installed in conformance with all applicable standards, and shall be tested to withstand 2.5 times the maximum operating pressure or a min. 50 psi test pressure for 2 hrs.
- When the forceman is installed in a fill section, crushed stone, gravel or approved structural fill shall be installed.




**NOTE:**

- Restrictive measurements are to be taken from the toe of slope.



**INSTALLATION NOTES:**

- Stone size - use 3/4" min. Stone, or reclaimed or recycled concrete equivalent.
- Length - as required, but not less than 50 feet (except on a single residence lot where a 30 foot minimum length would apply).
- Thickness - not less than six (6) inches.
- Width - 10 foot minimum, but not less than the full width at points where ingress or egress occur. 24 ft if single entrance to site.
- Surface water - all surface water flowing or diverted toward construction entrances shall be piped across the entrance. If piping is impractical, a mountable berm with 5:1 slopes will be permitted.
- Maintenance - the entrance shall be maintained in a condition which will prevent tracking or flowing of sediment onto public right of way this may require periodic top dressing with additional stone as conditions demand and repair and/or cleanouts of any measures used to trap sediment. All sediment spilled, dropped, washed or tracked onto public right of way must be removed immediately.
- Washing - wheels shall be cleaned to remove sediment prior to entrance onto public right of way. When washing is required, it shall be done on an area stabilized with stone and which drains into an approved sediment trapping device.
- Periodic inspection and needed maintenance shall be provided after each rain.



**MODEL: SHEF40**

**R.P.M.** 1550

**MOTOR TYPE** SHADED POLE WITH THERMAL OVERLOAD, OIL FILLED

**MOTOR PROTECTION** AUTOMATIC RESET / OVERLOAD PROTECTED

HP	VOLTAGE	PHASE	NEC CODE	SERVICE FACTOR	FULL LOAD AMPS
4	115	1	-	1	12.0
	230				6.5

**Physical Data**



**DISCHARGE SIZE** 1 1/2" NPT

**SOLIDS SIZE** 3/4"

**IMPELLER TYPE** VORTEX

**CABLE LENGTH** 10' STANDARD  
20' OPTIONAL


**PAINT** PAINTED AFTER ASSEMBLY, DARK GREEN, WATER REDUCIBLE ENAMEL, ONE COAT, AIR DRIED.



**PROPOSED SEPTIC SYSTEM**


**VERT. SCALE: 1" = 4'**

**HORIZ. SCALE: 1" = 40'**



**NOTES:**

- The minimum required fill cover above the septic tank shall be 6 to 12 inches with a maximum cover depth of 24 inches. When required fill cover exceeds 24 inches, manhole extensions with steel frames and covers shall be installed and extended to finished grade. If the septic tank is rated for H-20 vehicle loading, the manholes, frames and covers shall be H-20 rated also.
- The dual compartment baffle is required on all septic tanks with a length "B" equal to or greater than 10 feet.
- For installations that require an overflow tank, a tank the same size as the septic tank shall be used. Dual compartment baffles are not required on overflow tanks regardless of the size.
- All pipes connecting to the tank shall be cut flush with the inside wall.
- Tank shall be manufactured by Mid Hudson Concrete Products, Inc.



LIQUID CAPACITY	A	B	C
1250 Gal.	60"	120"	67"

**PUMP CALCULATIONS:**

TOTAL FLOW = 800 GAL./DAY

LENGTH OF FIELDS: 400 L.F. W/24" TRENCHES

RATE OF PUMPING: BY DEMAND

**HEAD LOSS CALCULATION:**


TOTAL HEAD LOSS = STATIC LOSS + FRICTION LOSS

FROM DESIGN CALCULATIONS:

TDH = 24.5' + 0.4' = 25.0'


**NOTES:**

- The minimum required fill cover above the pump chamber shall be 6 to 12 inches with a maximum cover depth of 24 inches. When required fill cover exceeds 24 inches, manhole extensions with steel frames and covers shall be installed and extended to finished grade. If the pump chamber is rated for H-20 vehicle loading, the manholes, frames and covers shall be H-20 rated also.
- Pump shall be Hydromatic pump Model SHEF 40, 1-1/2" discharge, 4 HP, single phase, 1550 RPM, 3/4" solids handling, rated capacity of 19 GPM @ 25 FT TDH.
- Pump chamber as manufactured by Mid Hudson Concrete Products Inc.
- Pump settings may vary for tanks whose dimensions differ from those shown above. Contractor shall notify engineer of any change.
- All pipes connecting to the chamber shall be cut flush with the inside wall.
- Contractor shall supply and install control / alarm panel within building / basement or other approved location.
- Electrical Underwriters Certificate is required for all installations.




**NOTES:**

- Ends of all trenches are to be capped.
- Minimum 5' of soil between the bottom of absorption trench and presence of groundwater table and/or crushed rock.
- Maximum slope, 4 inch gravelly distribution lines (1/16" per ft) 0.5% maximum.
- Maximum slope, when dosing is provided (1/32" per ft) 0.25% maximum.




**NOTES:**

- Filter cloth to be fastened securely to post: steel either I or U type or 2" hardwood posts at top and mid section.
- When two sections of filter cloth adjoin each other they shall be overlapped by 6 inches and folded. Filter cloth shall be min. 100% stabilika 1140 or approved equal.
- Maintenance shall be performed as needed and material removed when "bubbles" develop in the silt fence.
- Excavate 4 inch trench along the lower perimeter of the site.
- Unroll a section at a time and position the post against the back (downstream) wall of the trench (net side away from direction of flow).
- Drive the post into the ground until the netting is approximately 2 inches from the trench bottom.
- Lay the toe-in flap of fabric onto the undisturbed bottom of the trench, backfill the trench and tamp the soil. Steeper slopes require an intercept trench.
- Join sections as shown above.



**NOTES:**

- Area chosen for stockpiling operations shall be dry and stable.
- Maximum slope of stockpile shall be 1:2.
- Upon completion of soil stockpiling, each pile shall be surrounded with either silt fencing or strawbales, then stabilized with vegetation or covered.
- See detail for installation of silt fence.



**NOTES:**

- Filter cloth to be fastened securely to post: steel either I or U type or 2" hardwood posts at top and mid section.
- When two sections of filter cloth adjoin each other they shall be overlapped by 6 inches and folded. Filter cloth shall be min. 100% stabilika 1140 or approved equal.
- Maintenance shall be performed as needed and material removed when "bubbles" develop in the silt fence.
- Excavate 4 inch trench along the lower perimeter of the site.
- Unroll a section at a time and position the post against the back (downstream) wall of the trench (net side away from direction of flow).
- Drive the post into the ground until the netting is approximately 2 inches from the trench bottom.
- Lay the toe-in flap of fabric onto the undisturbed bottom of the trench, backfill the trench and tamp the soil. Steeper slopes require an intercept trench.
- Join sections as shown above.

**Site Design Consultants**  
Civil Engineers • Land Planners  
251-F Underhill Avenue, Yorktown Heights, NY 10598  
(914) 962-4488 - Fax: (914) 962-7386  
www.sitedesignconsultants.com

Project # 17-50

Engineer: Joseph C. Riha, P.E.  
NYS Lic. No. 64431

Revisions:

No.	Date	Comments
1.	6-6-18	H.D. Comm.
2.	6-22-18	DEP Comm.
3.	8-21-18	H.D. & DEP Comm.
4.	10-11-18	HOUSE SUBMITTAL
5.	2-01-19	HOUSE SUBMITTAL

SCALE: 1" = 20'

DRAWN BY: MD

DATE: 11-3-17

**SEPTIC TANK DETAILS**

SITE PLAN PREPARED FOR: CONTE HOMES, INC.  
1550 JOURNEY'S END ROAD  
Westchester County, NY  
Town of Yorktown

Sheet 7 of 7