

Q&A1 for Fencing Bid

- 1.) The specifications are referring to the line posts as HD black coated.... Do you mean "heavy duty? If so, is SS40 pipe acceptable? **Yes Schedule 40**
- 2.) The specifications state the line posts should be 20' high. This is incorrect, is it not? They should be 16ft high, correct? **Yes should be 16 & 16 in the drawing**
- 3.) The specifications state that the mid rails should be 2-1/2". This is incorrect. Mid rails should all be 1-5/8" correct? **No, 2 & 1/2 is accurate**
- 4.) When cutting and removing the existing netting at the new 6-5/8" end posts, how are we to reattach it to the new posts? Zip ties can be used, however it may not be able to slide up and down with the existing fully system. **NO NETTING SHALL BE CUT. Please see additional bid for 16' fence to replace netting.**
- 5.) To what extent are we required to excavate and remove the existing concrete footing? 6" below grade? 12"? **6 inches below grade or removed and back filled.**