Q&A1 PICKLEBALL FENCING BID

I wanted to ask if there's a layout or any additional documentation available for the job site that you could share with us. The layout is the same as it is currently located at 2975 Stony St., Mohegan Lake, NY. Please feel free to visit.

Can you please clarify if you are looking for a total of 11 posts (e.g., 5 at 3" and 6 at 2-1/2") or a total of 22 posts (11 of each)? 3" end post and 3" gate post for a Quantity of 4, 2 1/2" line post Quantity of a minimum of 7 depending on the installers layout.

What amount of the 4' high and the 6' high fencing will be removed? Contractor would have to do this project in 3 phases. First removal all fencing fabric, then on a different date install poles and footings, then at the completion of the new court install new fencing fabric.

Regarding the 4-foot fence, will the court be resurfaced? If not, and we remove the posts with their footings to install new ones, would you like us to pour the cement flush so it levels with the existing surface? Level with existing sub-surface.

When removing the existing fence, posts will be pulled out of then ground. This will probably pull up the existing asphalt along with it (especially when removing the 4ft fence which is in the middle of the court). Who will be responsible for the existing surface? Is the town intending to resurface the court? YES

When setting new posts for 4ft high fence, will we be setting concrete footings up to surrounding surface? Concrete footings Sleeves up to stone base, separate vendor will be responsible for asphalt

Or are we required to cold patch the top of each footing with asphalt? If we need to use asphalt, are we required to coated the top to match existing service? Posts must be Sleeved

Is a bid bond/payment & performance bond required? The documents state that the information would be in the Instructions to Bidders". There is no information. Are we to assume that it is waived? No bonds required

Are permits required from the town? Yes, but fee waived for town project

Regarding the removal and disposal of existing 4ft high and 6ft high fences, is it acceptable to remove footings to a depth of approximately 6" below grade? Or are footings to be removed in their entirety? In their entirety

All posts for new 8ft high fencing (line posts, and end posts) shall be 3" in diameter, correct? Correct

Posts for new 4ft high fencing shall consist of 3" diameter end posts, and 2-1/2" diameter line posts, correct? Correct

What size posts are required for the gate posts? Is 3" in diameter acceptable? Yes What size pipe is required to be used for the gate frames? 1-5/8" in diameter? 2" in diameter? 2"

What type of pipe shall be used? SS20? SS40? SS40

Is there a drawing available depicting the layout? Current Fence on location, bidder welcome to site visit.

Is there a detail available depicting the fence? No