# TOWN OF YORKTOWN SERVICES AND PUBLIC WORKS CONTRACTS BID

## GRANITE KNOLLS SPORTS & RECREATION COMPLEX

# **ADDENDUM #2**

### **ADDENDUM # 2 REFERS TO FOLLOWING:**

- ITEMIZED PROPOSAL & PROJECT BID SHEET
- **TECHNICAL SPECIFICATIONS SECTION 0401 & SECTION 0803**

### **CHANGE DESCRIPTION:**

- 1. ADD ITEMIZED PROPOSAL & PROJECT BID SHEET IP4 OF 8
- 2. SECTION 0401 CAST-IN PLACE CONCRETE
  - REPLACE THE FIRST PAGE OF THIS SECTION WITH PAGE 0401-1.
     SECTION 0402 CAST-IN-PLACE CONCRETE CURB (0402-1) IS AN INCORRECT PAGE.
- 3. SECTION 0803 ATHLETIC FIELD LIGHTING
  - REMOVE AND REPLACE PAGE 0801-5 OF THIS SECTION WITH PAGE 0803-5. SECTION 0801-5 IS AN INCORRECT PAGE.

# Town of Yorktown Parks & Recreation Granite Knolls Sports & Recreation Complex Project Town of Yorktown Project No. 01-17 Itemized Proposal & Project Bid - Sheet 4 of 8

	Prepared by
988:	Date

item #	Unit	Quanity	Description	Line Total
0601.4	4	265	Swale - Grass/Rip-Rap	
			per LF	64
0602	H	530	Furnish and finstall Sanitary Sewers	
			∃d bed	64
0701	EA	37	Precase Concrete Catch Basins	
			per EA	977
0702	EA	2	Precast Concrete Manholes	
			per EA	w
0703	EA.	C	Sewage Pumping Station	
			per EA	673-
0704	rs	-	Stormwater Management System Basins (Pocket Wetlands)	
			S7 Jabel	
0801	EA	21	Site Lighting	
			per EA	ůn.
2080	57	-	Building Services - General Plumbing & Electrical Work	
			per LS	us.

### SECTION 0401

### **CAST-IN-PLACE CONCRETE**

### PART 1: WORK

### 1.01 DESCRIPTION

Under this work, the Contractor shall furnish and install all materials, equipment, labor and services required for cast-in place concrete structures. Work includes the installation of formwork, reinforcement, expansion joints, special formwork or form liners for concrete with smooth finishes and other items listed herein within the site.

Included in this item are the following work at the locations shown on the Contract Documents, details and these specifications

- A. Concrete Pads Maintenance Building, Dugouts, Concession Stand, Restroom, and Miscellaneous concrete required.
- B. Concrete Foundations Maintenance Building, Dugouts, Concession Stand, Restroom.
- C Work ordered by the Engineer.

The Contractor shall coordinate his work and shall allow ample time and facility for the Work of other Divisions to be installed.

### 1.02 RELATED WORK SPECIFIED ELSEWHERE

- A. Section 0206 Gravel Parking Area
- B. Section 0402 Cast-In-Place Concrete Curbs
- C. Section 0501 Water Main
- D. Section 0502 Force Main
- E. Section 0701 Precast Concrete Catch Basins
- F. Section 0702 Precast Concrete Manholes
- G. Section 0703 Sewage Pumping Station
- H. Section 0801 Site Lighting
- Section 0803 Athletic Field Lighting
- J. Section 0902 Outdoor Equipment
- K. Section 0903 Dugouts
- L. Section 0906 Site Restoration
- M. Section 0907 Traffic Signs
- N. Section 0908 Timber Guard Rall

### 1.03 REFERENCES

- A. Except as shown or specified otherwise, the Work of this Section shall conform to the requirements of American Concrete Institute (ACI) and American Society for Testing and Materials (ASTM) documents.
  - ACI 301-05: Specification for Structural Concrete for Buildings.
  - 2. ACI 302.1R-04. Guide for Concrete Floor and Slab Construction.
  - ACI 302.2R-06. Guide for Concrete Slabs that Receive Moisture- Sensitive Flooring Materials

### 3.04 DELIVERY TIMING

- A. Delivery Timing Equipment On-Site: The Town will purchase and furnish Musco's Light-Structure System<sup>TM</sup> with TLC for LED<sup>TM</sup> a minimum of 4 weeks prior installation. The Contractor shall send a written request to purchase with an installation schedule to the Town a minimum of 12 weeks prior to the actual installation of the Athletic Field Lighting.
- B. The Contractor shall coordinate his activities with the Manufacturer of the Lighting System and shall allow ample time and facility for the work of this and other Sections to be installed.

### 3.05 FIELD QUALITY CONTROL

THIS SECTION LEFT BLANK

### PART 4: MEASUREMENT AND PAYMENT

4.01 METHOD OF MEASUREMENT

THIS SECTION LEFT BLANK

### 4.02 BASIS OF PAYMENT

Payment for all Work under this item shall be at the Lump Sum bid and shall include the cost of all permits, inspections, testing, labor, materials and equipment necessary to complete the work as shown on the Contract Drawings and as specified herein.

The Contractor shall install a complete lighting system as furnished by the Town. Included in this work item shall include the cost of concrete backfill for the precast concrete bases, underground service, conduit, wire, pull boxes, etc. to form an operable athletic field lighting at the locations shown on the Contract Drawlings. This work shall not be limited to all labor, materials and equipment including but not limited to wiring from main panel to each light assembly, excavation, trenching, disposal of surplus materials, other connections and any incidental work required to complete the work as specified in the Contract Documents and Specifications, and to the satisfaction of the Engineer.

- 1. Baseball Field
- Multi-purpose Field 1.
- Multi-purpose Field 2.
- 4 Walkways Lighting as shown. Additional site lighting will be paid under Item 0801 Site Lighting.

The lighting system shall be completely operational, tested, and free from fault.

**END OF SECTION**